

UNIVERSITY OF CALIFORNIA, SANTA BARBARA

BERKELEY • DAVIS • IRVINE • LOS ANGELES • MERCED • RIVERSIDE • SAN DIEGO • SAN FRANCISCO



SANTA BARBARA • SANTA CRUZ

OFFICE OF DESIGN & CONSTRUCTION SERVICES and PHYSICAL FACILITIES

CONTRACTING SERVICES
Building 439
Santa Barbara, California 93106-1030
Telephone (805) 893-3356
Fax (805) 893-8592

SENT VIA: FAX ON THIS DATE
 E-MAIL
 POSTED ON UCSB PLANROOM AND WEBSITE

HOLDERS OF PLANS AND SPECIFICATIONS:

Fire Alarm Mass Notification System, Campbell Hall
FM140241S/100-60
Addendum No. 5

February 7, 2014

Enclosed is **ADDENDUM NO. 5** to the Construction Documents on the above-captioned project.

The Bid date is Friday, February 14, 2014 at 2:30PM to be held at:

CONTRACTING SERVICES
Facilities Management, Bldg. 439,
Door #E, Reception Counter
University of California, Santa Barbara
Santa Barbara, CA 93106-1030.

Late arrivals shall be disqualified. Please allow time for unforeseen traffic delays, securing a parking permit and potential parking problems.



Greg Moore,
Associate Director, Contracting Services

ADDENDUM NO. 5

to the

CONSTRUCTION DOCUMENTS

February 7, 2014

GENERAL

The following changes, additions or deletions shall be made to the following document(s) as indicated; all other conditions shall remain the same.

I. **INFORMATION AVAILABLE TO BIDDERS**

Item No.

1-1.

ITEM 6, REPORTS: ADD the following:

“c) Bulk Asbestos Analysis, by Forensic Analytical, dated 08/27/01, (attached 2 pages).”

II. **SPECIFICATIONS**

Item No.

2-1.

Specifications, Division 1, Section 01010 – Summary of Work, 1.01 – Work Required by Contract Documents: ADD A(1)(a):

“a. Contractor shall coordinate with the University Representative any work that will require the penetration or disturbance of asbestos containing fireproofing or asbestos containing acoustical ceiling in the mechanical/electrical room, Rm. 1301, in the lobby area, control room or any other area where asbestos spray applied acoustical ceiling or fireproofing is present. Work is to be done by the University. The University is not responsible for any penetrations or clean-up of asbestos containing sound insulation or pipe insulation found in the attic area. If asbestos in the attic area is disturbed or damaged, Contractor is to stop work immediately and contact the University Representative and any abatement or clean up will done by the University and charged to the Contractor. (See also Division 1, Section 01565 – Hazardous Material Procedures.)”

END OF ADDENDUM NO. 5



Bulk Asbestos Analysis

(EPA Method 600/R-93-116, Visual Area Estimation)

U.C. Santa Barbara
Project Manager
Environmental Health & Safety
Building 565 Mesa Road
Santa Barbara, CA 93106

Client ID: 5151
Report Number: B032434
Date Received: 08/24/01
Date Analyzed: 08/27/01
Date Printed: 08/27/01
First Reported: 08/27/01

Job ID / Site: JOB: Cambell Hall Electrical Rood - Cambell Hall 528

FASI Job ID: 5151-212

Sample Number	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
---------------	------------	---------------	------------------	---------------	------------------	---------------	------------------

CAMPBELL-PLM-01	10112696	Chrysotile	15 %				
------------------------	----------	------------	------	--	--	--	--

Layer: Off-White Semi-Fibrous Material

Total Composite Values of Fibrous Components: Asbestos:(15%) Cellulose (2%) Fibrous Glass (ND)
Comment:Collected on 08/21/2001

CAMPBELL-PLM-02	10112697	Chrysotile	15 %				
------------------------	----------	------------	------	--	--	--	--

Layer: Off-White Semi-Fibrous Material

Total Composite Values of Fibrous Components: Asbestos:(15%) Cellulose (2%) Fibrous Glass (ND)
Comment:Collected on 08/21/2001

CAMPBELL-PLM-03	10112698	Chrysotile	15 %				
------------------------	----------	------------	------	--	--	--	--

Layer: Off-White Semi-Fibrous Material

Total Composite Values of Fibrous Components: Asbestos:(15%) Cellulose (2%) Fibrous Glass (ND)
Comment:Collected on 08/21/2001

James Flores, Laboratory Supervisor, Hayward Laboratory

Note: Limit of Quantification ('LOQ') = 1%. 'Trace' denotes the presence of asbestos below the LOQ. 'ND' = 'None Detected'.

Analytical results and reports are generated by Forensic Analytical at the request of and for the exclusive use of the person or entity (client) named on such report. Results, reports or copies of same will not be released by Forensic Analytical to any third party without prior written request from client. This report applies only to the sample(s) tested. Supporting laboratory documentation is available upon request. This report must not be reproduced except in full, unless approved by Forensic Analytical. The client is solely responsible for the use and interpretation of test results and reports requested from Forensic Analytical. This report must not be used by the client to claim product endorsement by NVLAP or any other agency of the U.S. Government. Forensic Analytical is not able to assess the degree of hazard resulting from materials analyzed. Forensic Analytical reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

