

UNIVERSITY OF CALIFORNIA, SANTA BARBARA

BERKELEY • DAVIS • IRVINE • LOS ANGELES • MERCED • RIVERSIDE • SAN DIEGO • SAN FRANCISCO



SANTA BARBARA • SANTA CRUZ

OFFICE OF DESIGN & CONSTRUCTION SERVICES and PHYSICAL FACILITIES

CONTRACTING SERVICES  
Building 439  
Santa Barbara, California 93106-1030  
Telephone (805) 893-3356  
Fax (805) 893-8592

- SENT VIA:**  FAX ON THIS DATE  
 HAND DELIVERY ON THIS DATE  
 FEDERAL EXPRESS ON THIS DATE  
 UNITED PARCEL SERVICE ON THIS DATE

HOLDERS OF PLANS AND SPECIFICATIONS:

Francisco Torres Towers Deck Waterproofing  
and Repair, Bldg. 860  
Project No. FM070488S/292-71  
**Addendum No. 3**

June 20, 2007

Enclosed is **ADDENDUM NO. 3** to the Construction Documents on the above-captioned project.

Bid date is Wednesday, June 27, 2007 at 2:30 PM to be held at:

CONTRACTING SERVICES  
Facilities Management, Bldg. 439,  
Door #E, Reception Counter  
University of California, Santa Barbara  
Santa Barbara, CA 93106-1030.

Late arrivals shall be disqualified. Please allow time for unforeseen traffic delays, securing a parking permit and potential parking problems.

A handwritten signature in black ink, appearing to read "Anna Galanis".

Anna Galanis  
Director, Contracting Services

ADDENDUM NUMBER 3  
 to the  
 CONSTRUCTION DOCUMENTS

June 20, 2007

**GENERAL**

The following changes, additions or deletions shall be made to the following documents as indicated. All other conditions shall remain unchanged.

I. DRAWINGS

Item No.

1. Sheet T-1, Project Description, Item No. 6

**Revise** Item No. 6 to now read: "Replace all deck drain covers with new brass or stainless steel covers".

2. Sheet A-1, Walkway Plan

**Replace** note at Walkway 8 in its entirety.  
 "Slab walk is offset at this location and at door location in Walkway 7.  
 Repair both locations by means of a built-up slope transition with the Polymer Concrete Topping".

3. Sheet A-1, Walkway Plans

**Add** Part II General Notes

**Add** General Note No. 1.00, Planters

A. Planters identified as PLT1, PLT2, PLT3, PLT4, PLT5, PLT6 and PLT7 will be removed from the deck area by the University and returned to the deck area by the University after project completion. Planters PLT8, PLT9 and PLT10 remain in place and the coating of the base is part of this contract as indicated on Detail 12, Sheet PH-1.

4. Sheet A-1, Walkway Plans

**Add** General Note No. 2.00, Table of Coating Systems

<u>LOCATION</u>	<u>ELASTOMERIC DECK COATING</u>	<u>POLYMER CONCRETE TOPPING</u>
Walkway #1	No	Yes
Walkway #2	Yes	Yes
Walkway #3	No	Yes
Walkway #4	Yes	Yes
Walkway #5	Yes	Yes
Walkway #6	No	Yes
Walkway #7	No	Yes
Walkway #8	No	Yes

5. Sheet PH-1, Photos

**Omit** Photo No. 5 and associated note in its entirety.

6. Sheet PH-1 Photos

**Revise** note at Photo No. 6 to read: "Replace all drain covers with new".

END OF ADDENDUM NO. 3