

UNIVERSITY OF CALIFORNIA, SANTA BARBARA

BERKELEY • DAVIS • IRVINE • LOS ANGELES • MERCED • RIVERSIDE • SAN DIEGO • SAN FRANCISCO



SANTA BARBARA • SANTA CRUZ

OFFICE OF DESIGN & CONSTRUCTION SERVICES and PHYSICAL FACILITIES

CONTRACTING SERVICES
Building 439
Santa Barbara, California 93106-1030
Telephone (805) 893-3356
Fax (805) 893-8592

SENT VIA: FAX ON THIS DATE
 HAND DELIVERY ON THIS DATE
 FEDERAL EXPRESS ON THIS DATE
 UNITED PARCEL SERVICE ON THIS DATE

HOLDERS OF PLANS AND SPECIFICATIONS:

Harold Frank Hall Renovation-Rooms 4110/4118
Project No. FM080365S/981590

Addendum No. 1

March 31, 2009

Enclosed is **ADDENDUM NO. 1** to the Construction Documents on the above-captioned project.

Bid date is Tuesday, April 7, 2009 at 2:30 PM to be held at:

CONTRACTING SERVICES
Facilities Management, Bldg. 439,
Door #E, Reception Counter
University of California, Santa Barbara
Santa Barbara, CA 93106-1030.

Late arrivals shall be disqualified. Please allow time for unforeseen traffic delays, securing a parking permit and potential parking problems.

A handwritten signature in black ink, appearing to read 'Anna Galanis'.

Anna Galanis
Director, Contracting Services

ADDENDUM NUMBER 1
to the
CONSTRUCTION DOCUMENTS
March 31, 2009

GENERAL

The following changes, additions or deletions shall be made to the following document(s) as Indicated; all other conditions shall remain the same.

I. INFORMATION AVAILABLE TO BIDDERS

Item No.

1. 5. Reports, Add the following:
 - “7. Bulk Asbestos Analysis, HFH , Bldg 556, Rm 4110B, Date Received 3/26/2009, 1 pg, attached.
 8. Bulk Sample Log Asbestos, HFH, Bldg 556, Rm 4110B, Date 3/24/2009, prepared by G. Horstin, 1 pg, attached”

END OF ADDENDUM NO. 1



Bulk Asbestos Analysis

(EPA Method 600/R-93-116, Visual Area Estimation)

U.C. Santa Barbara
Project Manager
Design and Construction Svcs
Building 370
Santa Barbara, CA 93106

Client ID: 5151
Report Number: B122795
Date Received: 03/26/09
Date Analyzed: 03/26/09
Date Printed: 03/26/09
First Reported: 03/26/09

Job ID/Site: Harold Frank Hall Rm. Remodel - Bldg 556, Rm., 4110B

FALI Job ID: 5151-1381

Date(s) Collected: 03/24/2009

Total Samples Submitted: 3

Total Samples Analyzed: 3

Sample ID	Lab Number	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer	Asbestos Type	Percent in Layer
20090324-556-PLM-01	10852429						
Layer: White Drywall							ND
Layer: White Joint Compound							ND
Layer: Paint							ND
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %)	Fibrous Glass (10 %)						
20090324-556-PLM-02	10852430						
Layer: White Drywall							ND
Layer: White Joint Compound							ND
Layer: Paint							ND
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %)	Fibrous Glass (10 %)						
20090324-556-PLM-03	10852431						
Layer: White Drywall							ND
Layer: White Joint Compound							ND
Layer: Paint							ND
Total Composite Values of Fibrous Components:		Asbestos (ND)					
Cellulose (20 %)	Fibrous Glass (10 %)						

James Flores, Laboratory Supervisor, Hayward Laboratory

Note: Limit of Quantification ('LOQ') = 1%. 'Trace' denotes the presence of asbestos below the LOQ. 'ND' = 'None Detected'.

Analytical results and reports are generated by Forensic Analytical at the request of and for the exclusive use of the person or entity (client) named on such report. Results, reports or copies of same will not be released by Forensic Analytical to any third party without prior written request from client. This report applies only to the sample(s) tested. Supporting laboratory documentation is available upon request. This report must not be reproduced except in full, unless approved by Forensic Analytical. The client is solely responsible for the use and interpretation of test results and reports requested from Forensic Analytical. This report must not be used by the client to claim product endorsement by NVLAP or any other agency of the U.S. Government. Forensic Analytical is not able to assess the degree of hazard resulting from materials analyzed. Forensic Analytical reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified. All samples were received in acceptable condition unless otherwise noted.

