

UNIVERSITY OF CALIFORNIA, SANTA BARBARA

BERKELEY • DAVIS • IRVINE • LOS ANGELES • MERCED • RIVERSIDE • SAN DIEGO • SAN FRANCISCO



SANTA BARBARA • SANTA CRUZ

OFFICE OF DESIGN & CONSTRUCTION SERVICES and PHYSICAL FACILITIES

CONTRACTING SERVICES
Building 439
Santa Barbara, California 93106-1030
Telephone (805) 893-3356
Fax (805) 893-8592

SENT VIA: FAX ON THIS DATE
 HAND DELIVERY ON THIS DATE
 FEDERAL EXPRESS ON THIS DATE
 UNITED PARCEL SERVICE ON THIS DATE

HOLDERS OF PLANS AND SPECIFICATIONS:

ESSB Communications Inside Wiring, Bldgs 275, 276, &
277
Project No. FM090203S/981240
Addendum No. Three

December 22, 2008

Enclosed is **ADDENDUM NO. Three** to the Construction Documents on the above-captioned project.

Bid date is Wednesday, January 7, 2009 to be held at:

CONTRACTING SERVICES
Facilities Management, Bldg. 439,
Door #E, Reception Counter
University of California, Santa Barbara
Santa Barbara, CA 93106-1030.

Late arrivals shall be disqualified. Please allow time for unforeseen traffic delays, securing a parking permit and potential parking problems.

A handwritten signature in black ink, appearing to read "Anna Galanis".

Anna Galanis
Director, Contracting Services

ADDENDUM NUMBER THREE

to the

Construction Documents
December 22, 2008

GENERAL

The following changes, additions or deletions shall be made to the following document(s) as Indicated; all other conditions shall remain the same.

I DRAWINGS:

Item No.

1. Dwg. T-14, GGSE Rm. 1006

Change Drawing Note 1 to read: "Furnish and install 12" ladder rack 7' Aff. Fixed to top of comm racks."

2. Dwg. T-15, GGSE Rm. 1102

Change Drawing Note 1 to read: "Furnish and install 12" ladder rack 7' Aff. Fixed to top of comm racks."

3. Dwg. T-16, GGSE Rm. 2262

Change Drawing Note 1 to read: "Furnish and install 12" ladder rack 7' Aff. Fixed to top of comm racks."

4. Dwg. T-17, GGSE Rm. 2156

Change Drawing Note 1 to read: "Furnish and install 12" ladder rack 7' Aff. Fixed to top of comm racks."

5. Dwg. T-18, GGSE Rm. 3157

Change Drawing Note 1 to read: "Furnish and install 12" ladder rack 7' Aff. Fixed to top of comm racks."

6. Dwg. T-19, GGSE Rm. 3268

Change Drawing Note 1 to read: "Furnish and install 12" ladder rack 7' Aff. Fixed to top of comm racks."

7. Dwg. T-20, GGSE Rm. 4002B

Change Drawing Note 1 to read: “Furnish and install 12” ladder rack 7’ Aff. Fixed to top of comm racks.”

8. Dwg. T-21, GGSE Rm. 4105A

Change Drawing Note 1 to read: “Furnish and install 12” ladder rack 7’ Aff. Fixed to top of comm racks.”

9. Dwg. T-29, L&S Rm. 1327

Change Drawing Note 1 to read: “Furnish and install 12” ladder rack 7’ Aff. Fixed to top of comm racks.”

10. Dwg. T-30, L&S Rm. 1102A

Change Drawing Note 1 to read: “Furnish and install 12” ladder rack 7’ Aff. Fixed to top of comm racks.”

11. Dwg. T-31, L&S Rm. 2401

Change Drawing Note 1 to read: “Furnish and install 12” ladder rack 7’ Aff. Fixed to top of comm racks.”

12. Dwg. T-32, L&S Rm. 2106

Change Drawing Note 1 to read: “Furnish and install 12” ladder rack 7’ Aff. Fixed to top of comm racks.”

13. Dwg. T-33, L&S Rm. 3106

Change Drawing Note 1 to read: “Furnish and install 12” ladder rack 7’ Aff. Fixed to top of comm racks.”

14. Dwg. T-34, L&S Rm. 3401

Change Drawing Note 1 to read: “Furnish and install 12” ladder rack 7’ Aff. Fixed to top of comm racks.”

15. Dwg. T-35, L&S Rm. 4104A

Change Drawing Note 1 to read: “Furnish and install 12” ladder rack 7’ Aff. Fixed to top of comm racks.”

16. Dwg. T-36, L&S Rm. 4401

Change Drawing Note 1 to read: “Furnish and install 12” ladder rack 7’ Aff. Fixed to top of comm racks.”

17. Dwg. T-39, CFTVNM Floor 1

Change Drawing Note 1 to read: “Furnish and install 12” ladder rack 7’ Aff. Fixed to top of comm racks.”

18. Dwg. T-14, GGSE Rm. 1006

Change Drawing Note 3 to read: “Wire basket shall be furnished and installed as required to support station cable between entrance of general contractor provided wire basket and patch panels.”

19. Dwg. T-15, GGSE Rm. 1102

Change Drawing Note 3 to read: “Wire basket shall be furnished and installed as required to support station cable between entrance of general contractor provided wire basket and patch panels.”

20. Dwg. T-16, GGSE Rm. 2262

Change Drawing Note 3 to read: “Wire basket shall be furnished and installed as required to support station cable between entrance of general contractor provided wire basket and patch panels.”

21. Dwg. T-17, GGSE Rm. 2156

Change Drawing Note 3 to read: “Wire basket shall be furnished and installed as required to support station cable between entrance of general contractor provided wire basket and patch panels.”

22. Dwg. T-18, GGSE Rm. 3157

Change Drawing Note 3 to read: “Wire basket shall be furnished and installed as required to support station cable between entrance of general contractor provided wire basket and patch panels.”

23. Dwg. T-19, GGSE Rm. 3268

Change Drawing Note 3 to read: “Wire basket shall be furnished and installed as required to support station cable between entrance of general contractor provided wire basket and patch panels.”

24. Dwg. T-20, GGSE Rm. 4002B

Change Drawing Note 3 to read: “Wire basket shall be furnished and installed as required to support station cable between entrance of general contractor provided wire basket and patch panels.”

25. Dwg. T-21, GGSE Rm. 4105A

Change Drawing Note 3 to read: “Wire basket shall be furnished and installed as required to support station cable between entrance of general contractor provided wire basket and patch panels.”

26. Dwg. T-29, L&S Rm. 1327

Change Drawing Note 3 to read: “Wire basket shall be furnished and installed as required to support station cable between entrance of general contractor provided wire basket and patch panels.”

27. Dwg. T-30, L&S Rm. 1102A

Change Drawing Note 3 to read: “Wire basket shall be furnished and installed as required to support station cable between entrance of general contractor provided wire basket and patch panels.”

28. Dwg. T-31, L&S Rm. 2401

Change Drawing Note 3 to read: “Wire basket shall be furnished and installed as required to support station cable between entrance of general contractor provided wire basket and patch panels.”

29. Dwg. T-32, L&S Rm. 2106

Change Drawing Note 3 to read: “Wire basket shall be furnished and installed as required to support station cable between entrance of general contractor provided wire basket and patch panels.”

30. Dwg. T-33, L&S Rm. 3106

Change Drawing Note 3 to read: “Wire basket shall be furnished and installed as required to support station cable between entrance of general contractor provided wire basket and patch panels.”

31. Dwg. T-34, L&S Rm. 3401

Change Drawing Note 3 to read: “Wire basket shall be furnished and installed as required to support station cable between entrance of general contractor provided wire basket and patch panels.”

32. Dwg. T-35, L&S Rm. 4104A

Change Drawing Note 3 to read: “Wire basket shall be furnished and installed as required to support station cable between entrance of general contractor provided wire basket and patch panels.”

33. Dwg. T-36, L&S Rm. 4401

Change Drawing Note 3 to read: “Wire basket shall be furnished and installed as required to support station cable between entrance of general contractor provided wire basket and patch panels.”

34. Dwg. T-39, CFTVNM Floor 1

Change Drawing Note 3 to read: “Wire basket shall be furnished and installed as required to support station cable between entrance of general contractor provided wire basket and patch panels.”

35. Dwg. T-9 GGSE Floor 1

Add Drawing Note 3 to read: “WAP cables to terminate on separate 24 port patch panels at one (1) Comm room at each floor.”

36. Dwg. T-10 GGSE Floor 2

Add Drawing Note 3 to read: “WAP cables to terminate on separate 24 port patch panels at one (1) Comm room at each floor.”

37. Dwg. T-11 GGSE Floor 3

Add Drawing Note 3 to read: “WAP cables to terminate on separate 24 port patch panels at one (1) Comm room at each floor.”

38. Dwg. T-12 GGSE Floor 4

Add Drawing Note 3 to read: “WAP cables to terminate on separate 24 port patch panels at one (1) Comm room at each floor.”

39. Dwg. T-24 L&S Floor 1

Add Drawing Note 4 to read: “WAP cables to terminate on separate 24 port patch panels at one (1) Comm room at each floor.”

40. Dwg. T-25 L&S Floor 2

Add Drawing Note 3 to read: “WAP cables to terminate on separate 24 port patch panels at one (1) Comm room at each floor.”

41. Dwg. T-26 L&S Floor 3

Add Drawing Note 2 to read: “WAP cables to terminate on separate 24 port patch panels at one (1) Comm room at each floor.”

42. Dwg. T-27 L&S Floor 4

Add Drawing Note 2 to read: “WAP cables to terminate on separate 24 port patch panels at one (1) Comm room at each floor.”

43. Dwg. T-3 General Specifications

Add Note 11 to read: “Pull strings at existing Comm conduits are provided by others.”

44. Dwg. T-24 L&S Floor 1

Change Reference Note 5 to read: “NOT USED”

45. Dwg T-7 Comm Riser

Replace Drawing T-7 Comm Riser dated 11/24/2008 in its entirety with drawing T-7 Comm Riser dated 12/22/08.

46. Dwg T-8 Cable Pull Lists

Replace Drawing T-8 Cable Pull Lists dated 11/24/2008 in its entirety with drawing T-7 drawing Cable Pull Lists dated 12/22/08.

END OF ADDENDUM NO. THREE