

UNIVERSITY OF CALIFORNIA, SANTA BARBARA

BERKELEY • DAVIS • IRVINE • LOS ANGELES • MERCED • RIVERSIDE • SAN DIEGO • SAN FRANCISCO



SANTA BARBARA • SANTA CRUZ

OFFICE OF DESIGN & CONSTRUCTION SERVICES and PHYSICAL FACILITIES

CONTRACTING SERVICES
Building 439
Santa Barbara, California 93106-1030
Telephone (805) 893-3356
Fax (805) 893-8592

SENT VIA: FAX ON THIS DATE
 HAND DELIVERY ON THIS DATE
 FEDERAL EXPRESS ON THIS DATE
 UNITED PARCEL SERVICE ON THIS DATE

HOLDERS OF PLANS AND SPECIFICATIONS:

Housing & Residential Services, Ortega Office Remodel
Project No. FM070019S/987670

Addendum No. 2

February 16, 2007

Enclosed is **ADDENDUM NO. 2** to the Construction Documents on the above-captioned project.

Bid date is **Friday, February 23, 2007 at 2:30PM** to be held at:

CONTRACTING SERVICES
Facilities Management, Bldg. 439,
Door #E, Reception Counter
University of California, Santa Barbara
Santa Barbara, CA 93106-1030.

Late arrivals shall be disqualified. Please allow time for unforeseen traffic delays, securing a parking permit and potential parking problems.

A handwritten signature in black ink, appearing to read "Anna Galanis".

Anna Galanis
Director, Contracting Services

ADDENDUM NUMBER 2
to the
CONSTRUCTION DOCUMENTS

February 16, 2007

General

The following changes, additions or deletions shall be made to the following documents(s); and all other conditions shall remain the same.

I . SPECIFICATIONS .

Item No.

1. Section 09260, GYPSUM BOARD SYSTEMS, Part 2, PRODUCTS, 2.01 MANUFACTURERS – GYPSUM BOARD SYSTEM, **ADD**
B to read as follows: “Acoustical Sealant: Non-hardening, non-skinning, for use in conjunction with gypsum board, manufactured by USG< GOLD Bond, or equal.”
2. Section 09260, GYPSUM BOARD SYSTEMS, Part 2, PRODUCTS,, **ADD**
2.05, ACOUSTICAL INSULATION, A to read as follows:
“Place acoustical insulation in partitions, tight with spaces, around cut openings, behind and around electrical and mechanical items within or behind partitions and tight to items passing through partitions.”
3. Section 09260, GYPSUM BOARD SYSTEMS, Part 3, EXECUTION,3.04 GYPSUM BOARD INSTALLATION, **ADD**
F to read as follows: “Install acoustical sealant at gypsum board perimeter at floor, ceiling and abutting walls. Caulk all penetrations of partitions by conduit, pipe, ductwork, and rough-in boxes.”
4. Section 09260, GYPSUM BOARD SYSTEMS, Part 3, Execution, **ADD**
3.07, Batt Insulation, to read as follows:. Contractor to install batt insulation in all new walls.

II . DRAWINGS

Item No.

1. Drawing A1A, SCHEDULES,Door Schedule, Door No.'s C & D, **CHANGE,**
Finish to read: “P”.

III . CLARIFICATIONS

Item No.

- 1 Purpose of Galvanized wall covering: Client requested wall finish
- 2 Storefront window layout: Correct layout is as shown on exterior elevations sheet A-5
- 3 Data/phone communications: Contractor to provide conduit, termination box, and ring/string to locations indicated. University will provide cabling.
4. 24x24 access panels to be fire rated:
- 5 Any abatement by UCSB staff: Previously done
- 6 See specifications section 09680 Part three paragraph A for existing carpet procedure.
- 7 Gypsum wall board termination at stucco ceiling to be butted to ceiling and caulked/puttied to form seamless joint
- 8 Topping/self leveling underlayment manufactures specifications may go from 0" to 3" in depth/thickness.

END OF ADDENDUM NO. 2